



Remarks:

- This contractor is responsible to supply and install new T5 LED tubes (L13 & L13a) to replace all T5 tubes of existing light panel (L14 & L14a) including modification works on existing lighting panel with all necessary accessories.
- LED tubes (L13 & L13a) shall be used for all new lighting panels and existing lighting panels (L14 & L14a).

03
LCP03

LIGHTING CIRCUIT PLAN

Scale: 1:100

LEGEND

1 WAY 1 GANG 電燈開關掣	1 WAY 1 GANG 電燈開關掣	1 WAY 1 GANG 電燈開關掣	1 WAY 1 GANG 電燈開關掣
1 WAY 2 GANG 電燈開關掣	1 WAY 2 GANG 電燈開關掣	1 WAY 2 GANG 電燈開關掣	1 WAY 2 GANG 電燈開關掣
TIMER (HOLIDAY SCHEDULE)	TIMER (HOLIDAY SCHEDULE)	TIMER (HOLIDAY SCHEDULE)	TIMER (HOLIDAY SCHEDULE)
TIMER MOTION SENSOR (CONFERENCE ROOM ONLY)	DAYLIGHT CONTROL	DAYLIGHT CONTROL	DAYLIGHT CONTROL

TENDER ADDENDUM NO. 1 (6 JULY 2022)

最終數量	數量	標誌	說明	最終數量	數量	標誌	說明	最終數量	數量	標誌	說明
		E	現有600 X 1200mm天花燈盤 (三管)			—	軌道天花射燈2 L03			E	隱藏式消防噴頭 (現存的)
		R	移位600 X 1200mm天花燈盤 (三管) L14			—	吊線燈 L04, L05, L10			R	隱藏式消防噴頭 (移動)
		N	新加600 X 1200mm天花燈盤 (三管) L14			⊙	吊燈1 L06			N	隱藏式消防噴頭 (新的)
		E	現有600 X 1200mm應急照明天花燈盤 (三管)			⊙	吊燈2 L07			E	1 WAY 1 GANG 電燈開關掣
		R	移位600 X 1200mm應急照明天花燈盤 (三管)			⊙	吊燈3 L08			R	1 WAY 2 GANG 電燈開關掣
		R	移位600 X 600mm天花燈盤 (三管) L14a			—	木條			N	TIMER
		N	新加600 X 600mm天花燈盤 (三管) L14a			—	高櫃			E	DAYLIGHT CONTROL
		⊙	單頭天花筒燈 L01			—	吊櫃			R	TIMER (HOLIDAY SCHEDULE)
		⊙	雙頭天花筒燈 (EMERGENCY LIGHT)			—	ACCESS PANEL			E	TIMER MOTION SENSOR
		⊙	可調教天花射燈 L02			—				N	L11 壁燈

Space Interior Solutions Ltd	PROJECT INFORMATION	PROJECT
30/F, Times Square, 118, Jaffe Road Hong Kong, China Tel: 2369 8888 Email: info@sis.com.hk Website: www.sis.com.hk	PROJECT ADDRESS: 8/F CHINA LIFE CENTRE, 18 HUNG LUEN RD, HUNGOM, KOWLOON	ISSUE FOR TENDER TENDER ADDENDUM NO. 1

SHEET INFO	SHEET NO.
CL	LCP03
DATE	2022.02.14
SCALE	1:100
PROJECT NO.	21014-HK-CL002