

- B2.3 Supply and installation of final circuit power installation, including:-
- ☐ MCB boards and accessories
 - ☐ Trunking and accessories
 - ☐ Cable, conduit and accessories
 - ☐ Socket outlets
 - ☐ Connection units
 - ☐ Floor Boxes
 - ☐ Power point as specified on the drawings
- B2.4 Supply and installation of final circuit lighting installation, including:-
- ☐ Switches
 - ☐ Motion sensors and by-pass switches if need
 - ☐ Lighting points for all lighting fittings as shown on the drawing
 - ☐ Timer and contactors
 - ☐ Trunking, cable, conduit and accessories
- B2.5 Alteration and addition of all existing Office light fittings (ceiling, trough, furniture etc.) including lamps transformer, ballast, wiring, conduit/ trunking, switch points as specified by the Lighting Designer.
- B2.6 Supply and installation of all new Office light fittings (ceiling, trough, furniture etc.) including lamps, transformer, ballast, wiring, conduit / trunking, switch points as indicated on the drawings & specified by the Lighting Designer.
- B2.7 Supply and installation of all emergency lighting (i.e. Exit Sign and battery pack for Office Lightings) as shown on drawings, including wiring, conduit/ trunking, switch points.
- B2.8 Supply and installation of trunking and conduit installation for AV system and intercom system.
- B2.9 Supply and installation of trunking and conduit installation for IT system, computer system and telephone system.
- B2.10 Supply and installation of trunking and conduit installation for Security system, i.e. CCTV system and door access system.
- B2.11 Supply and installation of the earthing protection including protective conductor for the low voltage distribution system and equipotential bonding to all extraneous conductive parts in the site area.
- ~~B2.12 Supply and installation of Motion Sensor Lighting Control System as specified in the tender drawings. Contractor shall be responsible for the modification of lighting circuits; addition of new motion sensor and programming work. (Deleted)~~
- ~~B2.13 Supply and installation of Timer Lighting Control System as specified in the tender drawings. Contractor shall be responsible for the modification of lighting circuits; addition of timer control panels and programming work. (Deleted)~~
- B2.14 Supply an installation of new emergency power supply including all necessary protective devices, cable wiring and cable containment provisions as shown in the Tender Drawings. **(Provision of incoming essential cable and accessories required shall be carried out by Landlord's Nominated Contractor under this Contract)**
- B2.16 Alternation of building's PA system and mobile phone antenna according to new layouts. Contractor shall be responsible for the addition of PA equipment such as amplifier and speaker if required. **(Work shall be carried out by Landlord's Nominated Contractor under this Contract)**