Schedule 5A - Furniture

25樓室內裝修工程						
Item	**Code**	**Description**	**Qty**	**Unit**	**Unit Price**	**Amount (HK$)**
		Furniture				
1	L1	Boardroom Table **Material:** Veneer table top, metal base **Size:** 2400W x 8400L x 750Hmm		no(s).		
2	L2	Boardroom Chair **Materials:** Leather finish w/. Chromed alloy aluminium 5-star base w/. Castors **Size:** 595W X650D X 965-1065HMM		no(s).		
3	L3	Leisure Area Table **Material:** Sintered Stone + Metal **Size:** 800 Dia X 750Hmm		no(s).		
4	L4	Leisure Area Table **Material:** Sintered Stone + Metal **Size:** 1000 Dia X 750Hmm		no(s).		
5	L5	Leisure Area Pantry Chair **Material:** Frame: White frame Backrest: PP (Polypropylene)backrest **Seat Cushion:** High-resilience foam / OS300 Series mesh **Base:** Fine-textured powder-coated sled base **Size**: D515*W505*H870		no(s).		
6	L6	Leisure Area Chair **Material:** Fabric Upholstery **Internal Material:** One-piece molded foam sponge **Craftsmanship:** Embossed fabric finish; bonded to foam using benzene-free adhesive; fully hand-upholstered **Base / Frame:** Premium steel tubing (ø22mm, 1.5 mm wall thickness) with a matte black frosted finish **Size:** 740*730*820		no(s).		
7	L7	Leisure Area Coffee Table **Description:** Veneer Top Metal Base **Size:** 800Dia X 280Hmm		no(s).		
8	L8	Open Shelves Cabinet **Description:** High Open Shelf with Height Adjustrable Shelves **Size:** *W610 x D450 x H2080* **Material:** Epoxy Polyester Powder Coated		no(s).		
9		Those items (if any) not mentioned above but necessary for completion the whole system properly under the intent of the Works (Please specified).				
		Remark: Tenderer/ Contractor should check and include hereunder any other outstanding items and works in accordance with the drawings, specifications, site visit, etc. for complete tender. NO CLAIMS relating to the works will be allowed afterward				
					To be carried to Summary of Tender	
					Sub-total of Schedule 5A (HK$)	